Government Green Financing & Zero-Working-Capital Solar Proposal

Executive Client Brief (Scenario A): Replacing grid power (Tk 10.80–15.20/kWh) and captive diesel (Tk 32.00–38.00/kWh) with fixed LCOE rooftop solar (Tk 2.45–3.20/kWh) without touching working capital or 13.5%–15.5% credit lines.

1. THREE GOVERNMENT-BACKED FINANCING PROGRAMS FOR FACTORY & MALL OWNERS

Financing Facility	Debt Coverage, Interest & Tenure	Regulatory Mechanism, Disbursing PFIs & Client Advantage
1. Tk 1,500 Crore Solar Allocation Fund *(Ordinance-2026 Rollout)*	**Up to 80% Project Debt** 4.5%–5.5% p.a. | **10-Year Tenure** Includes **1-Year Grace Period**	Backed by World Bank ($500M), AIIB ($500M), and ADB ($250M). Client pays **Tk 0 principal & interest for Months 1–12**; Year-1 bill savings reimburse initial equity. Disbursed via **IDCOL, BIFFL, BRAC Bank, City Bank, EBL, Prime Bank**.
2. Bangladesh Bank Green Refinancing & GTF	**70% to 80% Project Debt 4.0%–5.5% p.a.** (1%–2% BB base) **7 to 10 Years** (84 Monthly EMIs)	Bangladesh Bank mandates a **5% Green Finance target** on all scheduled banks. Bank **Sustainable Finance Departments (SFDs)** fast-track creditworthy C&I rooftop borrowers, disbursing funds directly against turnkey EPC milestones.
3. Zero-CapEx PPA / OPEX *(If Client Deploys 0% Cash)*	**100% SPV Funded (Tk 0 Client Cash)** **15-to-20-Year** PPA Contract	Ariel sets up a Special Purpose Vehicle (SPV) that secures the green loan and owns the plant. Client invests **Tk 0** and buys solar power at a **15%–20% discount to grid tariff** (Tk 8.80–9.20/kWh, escalated at 70% of future BERC hikes).

2. SELF-PAYING CASHFLOW WATERFALL & TAX INCENTIVES (ZERO LIQUIDITY STRAIN)

Financial & Operational Metric	500 kWp Industrial Benchmark	424 kWp Commercial / C&I Benchmark
Total Turnkey CapEx & 1% Duty Benefit	**Tk 2.58 Cr** (Grid) / **Tk 3.15 Cr** (BESS) *SRO 159-Law/2026 (1% duty) saves ~16%*	**Tk 218.78 Lakh** (@ Tk 51.60/Wp) *+2%–3% discount via Client ERQ USD LC*
Financing Split (Concessionary Debt / Equity)	75%–80% Green Debt / 20%–25% Equity	**80% Debt** (Tk 175.03L) / **20% Equity** (Tk 43.76L)
Months 1–12 Cashflow (1-Yr Grace Period)	**+Tk 6.80 Lakh/mo** savings | **Tk 0 Loan EMI**	**+Tk 7.03 Lakh/mo** gross bill displacement
Month 13+ Green Loan Monthly Installment	**Tk 4.10 Lakh / month** (at 4.5%–5.5% p.a.)	**Tk 2.43 Lakh / month** (4.5% fixed, 84 mos)
NET FREE CASH SURPLUS TO OWNER	**+Tk 2.70 Lakh / Month (Net Positive)**	**+Tk 4.59 Lakh / Month (From Month 1)**
Weekend Export Cash & Corporate Tax Shield	**Tk 10.50/kWh cash buyback** (~Tk 12.70L/yr on 65 closed days) + **Tk 12L–15L Tax Shield**	**5% Corporate Electricity Tax Rebate** + I-REC carbon credits (435t CO_2e/yr CBAM shield)
Payback, Levered Equity IRR & 25-Yr Profit	**3.4–3.8 Yrs | 49.6%–54.2% IRR | Tk 24.8–27.1 Cr**	**2.6 Years Payback | Tk 18.89 Crore Net Profit**

3. FOUR-STEP BANK SANCTION PROCEDURE, STATUTORY COMPLIANCES & CUSTOMS RULES

Execution Stage	Loan & Turnkey EPC Procedure	Mandatory Statutory & Customs Compliances
Step 1: Pre-Qualification & 3D Drone Audit	Inspect 12-month utility bills and conduct a complimentary 3-hour 3D LiDAR/RTK drone shading and roof survey.	**NEM 70% Cap Rule:** AC inverter capacity cannot exceed **70% of sanctioned load** (min. 715 kW load required for 500 kWp; cap 10 MW).
Step 2: Bankable Feasibility Dossier	Ariel compiles PVsyst/HelioScope simulation, 25-yr DSCR/IRR cashflow waterfall, Single Line Diagram (SLD), and compliance certificates.	**IEB Structural Certificate:** PEB/RCC roof verified for **15–22 kg/m^2** dead load & **BNBC 2020** wind uplift (150–288 km/h). **FSCD/RSC:** 1.2m fire lanes, AI AFCI & **OCEI Class A/B/C** supervisor sign-off.
Step 3: SFD / IDCOL Submission & Customs	Submit Bankable Feasibility Dossier via Client Corporate RM to Bank SFD desk or IDCOL Renewable Energy Desk for sanction.	**SRO 159-Law/2026 (0%–1% Duty):** Panels (`8541.43.00`), Inverters (`8504.40.90`), LFP BESS (`8507.60.00`) verified by **SREDA & BSTI** (IEC 61215/62109, UL 9540). Source 6063-T6 aluminum rails locally (avoids 58.6% duty on `7610.90.00`).
Step 4: Disbursement & Net-Metering COD	Bank disburses 75%–80% green loan in milestones; client pays 20% equity in 4 stages (or opens USD LC via ERQ account).	**Utility COD (15–30 Days):** Joint committee inspection (DESCO/DPDC/BREB/BPDB/WZPDCL/NESCO), live **Anti-Islanding Trip Test**, & **Class 0.2S/0.5S Bi-Directional Smart Meter** installation.

URGENT CUTOFF — LOCK IN THE TK 10.50/kWh CASH BUYBACK TARIFF BY FEBRUARY 28, 2027: Under the Power Division's September 1, 2026 directive, battery-integrated net-metered systems commissioned before **February 28, 2027** lock in a guaranteed **Tk 10.50/kWh cash buyback rate** (settled quarterly into your bank account) until February 28, 2030. Authorize our engineering team today for a **100% Free On-Site Drone & Structural Pre-Feasibility Audit** to initiate your Bankable Feasibility Dossier.

Issued By: Syed Akramul Hassan, Managing Director & CEO, Ariel Renewable Energy Limited

HQ: House 30, Road 07, Block C, Niketon, Gulshan-1, Dhaka-1212 • +880 1819 273458 • energy@arielmc.com