Ariel Renewable Energy Limited
Sovereign Green Infrastructure & Industrial Decarbonization

Commercial & Industrial Rooftop Solar Division
SREDA Registered Turnkey Solar EPC Partner • Reg: C-194820

EXECUTIVE COMMERCIAL QUOTATION — TURNKEY C&I; ROOFTOP SOLAR EPC

Quotation Ref:	AREL-QT-2026-F500	**Client Enterprise:**	**Ha-Meem Denim Processing Mills Ltd.**
Date / Validity:	05 Nov 2026 / 30 Days	**Site / Grid Load:**	Mawna, Gazipur (1,200 kVA HT-3 Grid)

1. SYSTEM CAPACITY & TIER-1 BLOOMBERGNEF SPECIFICATIONS

DC System Capacity & PV Modules	**500.00 kWp** | 855 Nos JA Solar / JinkoSolar 585Wp N-Type Bifacial TOPCon (Eff 22.8%, 30-Yr Warranty)
AC Inverters & Safety Architecture	**440.00 kW AC** | 4 Nos Huawei SUN2000-110KTL-M2 / Sungrow AFCI Smart String Inverters (IP66, PID Recovery)
Civil Mounting & Roof Integrity	Hot-Dip Galvanized Structural Steel (ASTM A123, ≥85µm), 15-Yr Watertight Seal, 180 km/h BNBC 2020
Electrical BOS & Protection	1.5kV TÜV Solar Cable, Type-II AC/DC Surge Arrestors, Dual Earth Pit (<1.0 Ω), Bi-Directional Net-Meter
Yield & Carbon Offset Estimates	Est. **720,000 kWh/Year** | 446 Metric Tons CO2e Abated/Year | Satisfies RE100 / EU CBAM Directives

2. COMMERCIAL INVESTMENT & CASH INCENTIVE BREAKDOWN

Turnkey Scope Description	Capacity	Rate / Wp	Total Amount (BDT)
Turnkey EPC Investment (500 kWp C&I; Rooftop System)	500 kWp	BDT 48.00	**BDT 24,000,000**
GOB / SREDA Cash Incentive Net Yield (4% Facilitated Benefit)	Government	-4.00%	(BDT 960,000)
NET CAPITAL OUTLAY POST-INCENTIVE (All-Inclusive)	**500 kWp**	**BDT 46.08**	**BDT 23,040,000**

3. BANGLADESH BANK 4.5% GREEN REFINANCING DEBT MODEL (ZERO WORKING CAPITAL IMPACT)

80% Bank Debt Facility (4.5% p.a.)	**BDT 19,200,000** (5-Yr Tenor)	**20% Equity Downpayment**	**BDT 4,800,000** (Tk 48.0 Lac)
Monthly Grid Savings (Tk 14.85)	**BDT 891,000** / month	**Net Free Cash Flow after EMI**	**+ BDT 533,000 / mo** (Day 1 Positive)

4. COMMERCIAL TERMS, PROJECT MILESTONES & WARRANTIES

- **Payment Milestones:** 20% on Contract Signing • 40% on Module/Inverter Port Clearance • 30% on Mechanical Erection • 10% on Net-Metering COD.
- **Project Execution:** Turnkey Commissioning & Net-Metering COD completed within 60–75 Calendar Days from site handover.
- **Warranties & SLA:** 15-Year Roof Watertight Guarantee • 25-Year PV Linear Output (84.8%) • 25-Year PR ≥ 80% SLA • Year-1 Free O&M; + Drone Thermography.

FOR ARIEL RENEWABLE ENERGY LIMITED
(Official Signature & Corporate Seal)

Syed Akramul Hassan
Managing Director & CEO | Ariel Group / Holdings

CLIENT ACCEPTANCE & MANDATE AWARD
Accepted & Agreed by Authorized Signatory:

Name / Title: _____

Signature & Company Seal: _____ Date: _____

FOR ARIEL RENEWABLE ENERGY LIMITED
(Official Signature & Corporate Seal)

Syed Akramul Hassan
Managing Director & CEO | Ariel Group / Holdings

CLIENT ACCEPTANCE & MANDATE AWARD
Accepted & Agreed by Authorized Signatory:

Name / Title: _____

Signature & Company Seal: _____ Date: _____

Corporate HQ: House - 30 (1st Floor), Road - 07, Block - C, Niketon, Gulshan-1, Dhaka-1212, Bangladesh
✎ : +880 2410 811 91 ■ : +880 1819 273 458 ✉ : info@arielenergybd.com ■ www.arielenergybd.com